



“Restore London provided an excellent service to us by thoroughly surveying the brick & stone facades at the IME, annotating and costing each individual repair in a completely open and transparent way in order that the client could easily verify and agree the scope of works.”

Jacky Campbell – Commercial Manager, Paragon

Scope of Works

Restore London were the preferred specialist with an initial brief to carry out a condition schedule of the external facades in order that a comprehensive survey could be compiled. The team utilised our electronic surveying/scheduling software to annotate the works required, with all repairs cross referenced to the facade drawings for ease of identification. The resultant survey was quickly & easily agreed by the Architect/Client & the RL crafts-team set about carrying out the works. Replacement imperial soft red bricks were identified & resourced through one of our many brick suppliers, as was the Portland stone for indenting. Remedial works to bricks included replacement, pointing, brick indenting and brick repairs. Works to the stonework included re-pointing, repairs and indenting & the cross drilling/pinning of cracks. Restoration works to the chimney stacks and extensive repairs to the balustrades. The fabric of the Institution's façade, purpose-built in 1899, is now waterproof with all possible areas of accelerated decay addressed.

Project Name:	IME
Location:	Bird Cage Walk, Westminster
Client:	IMechE
Principal Contractor:	Paragon
Duration:	12 Weeks
Completion Date:	May 2017
Value:	£330K

