


Spencer House - Phase 1 & 2









"Restore London's entire team from estimating & pre-contract, through delivery to aftercare have been excellent. I would have no hesitation in recommending them."

Rupert Hilton, Historic Building Surveyor & Director - Janus Associates

Scope of Works

Restore London were privileged to deploy their time-served Cleaners, Masons & Façade Restorers to carry out the specialist external cleaning, restoration and conservation works at the iconic Spencer House, London. The works involved specialist cleaning of the Portland Stone using an ammonium carbonate poultice, super-heated steam, and the JOS systems.

Our crafts trades indented the entablature, carried out matching mortar repairs (incorporating ceramic "T" armatures), repointing, nano-lime consolidation works & lime shelter coats to the statues.

Original iron cramps were also removed and replaced with stainless steel. The Project works also included leadwork repairs and replacement to the ornate cornice sections & new lead hopper heads.

Project Name:	Spencer House Phases 1 & 2
Location:	London
Client:	Spencer House Ltd
Principal Contractor:	Restore London Ltd
Duration:	Phase 1 – 6 weeks
	Phase 2 – 4 weeks
Completion Dates:	Phase 1 - 31August 20
	Phase 2 - 20 August 21
Value:	Phase 1 - £48K
	Phase 2 - £74K.

